

**FLOODPLAIN AREA
FIELD SAMPLING REPORT**

**SAUGET AREA 2 SITES
(SITES O, P, Q, R, S)**

SAUGET, ILLINOIS

Prepared for:

Sauget Area 2 Sites Committee
c/o Solutia
575 Maryville Centre Drive
P.O. Box 66760
St. Louis, Missouri 63141

Prepared by:

AMEC Earth and Environmental, Inc.
285 Davidson Avenue, Suite 100
Somerset, New Jersey 08873

June 24, 2003

TABLE OF CONTENTS

1.0	INTRODUCTION.....	1
2.0	SUMMARY OF SAMPLING PROGRAM.....	2
2.1	RECONNAISSANCE SURVEY OBJECTIVES.....	2
2.2	FIELD SAMPLING PROGRAM.....	3
2.2.1	<i>Vegetation Sampling</i>	4
2.2.2	<i>Invertebrate Sampling</i>	5
2.2.3	<i>Soil Sampling for Target Analytes</i>	6
2.2.4	<i>Soil Sampling for Earthworm Tests</i>	-
3.0	OVERVIEW OF FIELD PROGRAM ACTIVITIES	8
3.1	DAILY SYNOPSIS.....	8
3.2	DESCRIPTION OF THE SAMPLING LOCATIONS.....	9
4.0	DEVIATIONS FROM THE SAMPLING PLAN	13

FIGURES

Figure 1	Sauget Area 2 Sampling Sites
Figure 2	Sauget Area 2 Sampling Locations

TABLES

Table 1	Sauget Area 2 Vegetative Species List
Table 2	Terrestrial Invertebrate Sampling Matrix

APPENDICES

APPENDIX A	PHOTOGRAPH LOG
APPENDIX B	CHAIN OF CUSTODY FORMS
APPENDIX C	VOLUME 4 ADDENDUM

1.0 INTRODUCTION

In accordance with an Administrative Order of Consent (AOC) between the United States Environmental Protection Agency (USEPA) and the Respondents for the Sauget Area 2 Sites (the Site), a Remedial Investigation and Feasibility Study (RI/FS) was implemented in accordance with an approved Site Sampling Plan (SSP) (dated April 15, 2002). This Floodplain Area Field Sampling Report (FAFSR) describes the field activities that were outlined in the SSP and implemented as part of the RI/FS program. The field activities discussed in this FAFSR were used to collect data necessary to support the completion of the Baseline Ecological Risk Assessment (BERA). Specifically, the objectives of the field activities were to characterize the ecosystem associated with Floodplain portion of the site and to collect data that would be incorporated into the food chain models to be used as part of the BERA. The Floodplain Area field activities were completed between October 7 and October 10, 2002.

2.0 SUMMARY OF SAMPLING PROGRAM

The objective of the BERA is to evaluate the potential for adverse ecological impacts to occur as a result of the exposure of various ecological receptors to constituents of concern that might be present in the Floodplain area of the Site. The Site (Sauget Area 2 Sites) consists of five former disposal areas, Sites O, P, Q, R and S, adjacent, or in close proximity, to the Mississippi River (Figure 1). These five Sites were given letter designations by the Illinois Environmental Protection Agency (IEPA) in the 1980s. Two of these sites, Sites Q and R, are located on the wet side of the floodwall and levee, which is operated and maintained by the United States Army Corps of Engineers and the Metro East Sanitary District. The floodwall is designed to protect the City of East St. Louis and the Villages of Sauget and Cahokia from flooding. Sites O, P and S are located on the dry side of the floodwall and levee.

As per the SSP, field activities to collect ecological information within the Floodplain portion of the Sites to support the preparation of the BERA consisted of two separate events, a reconnaissance survey and the sampling event.

2.1 RECONNAISSANCE SURVEY OBJECTIVES

A reconnaissance survey was conducted in August 2002. The objectives of the reconnaissance survey were to gather information to provide a verbal and photographic description of the sites, finalize sampling locations, procedures, and to determine the number of biota samples that could be realistically collected during the sampling program. Specifically, the reconnaissance survey actions were as follows:

- Photodocument Sites O, P, Q, R, and S.
- Locate previous soil/waste characterization sample locations from the RI to help determine locations for collocated soil and biota samples from each Site.
- Finalize representative receptor species for use as assessment endpoints.

- Conduct a qualitative fauna/flora survey for the sole purpose of site characterization (Appendix C).
- Document direct and indirect (e.g., calls, scat, tracks) observations of terrestrial vertebrates.
- Determine the dominant vegetation species and relative abundance of the species for subsequent sampling.
- Determine the most appropriate sampling techniques.

2.2 FIELD SAMPLING PROGRAM

The sampling program was defined in the Final SSP. The activities included in the sampling program were as follows:

- At surface soil locations utilized as part of the RI/FS field activities, collect vegetation and terrestrial invertebrates (including beetles, crickets, grasshoppers, slugs, snails and lepidopteran larvae) (Appendix C) for chemical analyses of tissues. Vegetation and terrestrial invertebrates were to be collected at each of the RI/FS surface soil locations in Sites O, P, Q, R, and S. As will be discussed in the next item, eight additional surface soil samples were proposed as part of the Floodplain sampling activities with Site Q due to its relatively larger size. Vegetation and terrestrial invertebrates would also be collected at these eight additional sampling locations in Site Q. Concentrations of target analytes in biological tissue will be used in dietary exposure models for selected receptor species for extrapolation to assessment endpoints.
- Collect eight additional surface soil samples (0-6" from the ground surface) from the southern end of Site Q and analyze for standard organic and inorganic parameters (volatile organic compounds (VOCs), semivolatile organic compounds (SVOCs), pesticides and herbicides, polychlorinated biphenyls (PCBs), dioxins and furans, and metals) outlined in the SSP. Soil sample locations were verified during the field

reconnaissance effort and biased towards areas of viable wildlife habitat. These locations were collocated with vegetation and invertebrate sample locations.

- Collect surface soil samples (0-6") from each vegetation/invertebrate sampling location and submit to a laboratory for a 28-day bioaccumulation test using earthworms (*Eisenia foetida*) provided by the laboratory. At the completion of the test, worms were to be analyzed for tissue residue (Appendix C). Concentrations of target analytes in biological tissue are to be used in dietary exposure models for selected receptor species for extrapolation to assessment endpoints.
- Collect vegetation, invertebrates and surface soil for earthworm tests at offsite locations (Appendix C).

The terrestrial sampling event was conducted from October 7 to October 10, 2002. Figure 2 depicts the Floodplain sampling locations within the five Sites.

2.2.1 VEGETATION SAMPLING

The goal of the vegetation sampling was to collect a sufficient amount of plant matter from the dominant species for chemical analysis at each of the surface soil sampling locations in the five sites. As per the SSP, the sampling protocol for vegetation began with the classification of the vegetation at each location to determine the dominant species for each location. Following that action, sufficient sample material was collected to make a composite sample of 175 to 200 grams for laboratory analysis. Only aboveground portions (stems/leaves/seeds) were collected for chemical analysis. Vegetation was collected using decontaminated stainless steel scissors or shears. The composite was washed with distilled water to remove extraneous soil, placed in a sampling bag, and submitted to the laboratory under proper chain-of-custody procedures for chemical analyses.

A total of twenty-nine vegetation samples were collected (including one duplicate) from the five sites as well as from the off-site areas for background purposes. The vegetation samples were analyzed for SVOCs, pesticides/herbicides, PCBs, dioxins/furans, and metals. Vegetation samples were collected on October 8 and 9, 2002 by removing the plant from the ground by hand or by decontaminated scissors, when necessary. Sample were rinsed with distilled water then placed in containers for shipment to the laboratory under proper chain-of-custody. Samples were weighed to ensure a sufficient amount of plant material was collected. The following is a list of the sample identities, site locations and vegetative species collected (if recorded). The complete vegetative species list can be found in Table 1.

- Site O – Samples: PL-O-1, PL-O-2 and PL-O-3.
- Site P – Samples: PL-P-1, PL-P-2, PL-P-3 and PL-P-4.
- Site Q – Samples: PL-Q-9 (Small White Morning Glory), PL-Q-10 (Johnson Grass), PL-Q-11 (Johnson Grass), PL-Q-12 (Orchard Grass), PL-Q-13 (Orchard Grass), PL-Q-14 (Johnson Grass), PL-Q-15 (White Heath Aster), PL-Q-16, PL-Q-17 (Nettle), PL-Q-18, PL-Q-19 (Jumpseed and various grasses), PL-Q-20 (Jumpseed) and PL-Q-21 (Duplicate of PL-Q-12, Orchard Grass).
- Site R – Samples: PL-R-1, PL-R-2, PL-R-3, PL-R-4 and PL-R-5.
- Site S – Sample PL-S-1.
- Off site areas – Samples: PL-OS-2, PL-OS-3 and PL-OS-4.

2.2.2 INVERTEBRATE SAMPLING

The goal of invertebrate sampling was to obtain sufficient biomass for tissue analysis of the target compounds. A sufficient amount of specimens were to be collected to create a composite sample at each of the locations. The laboratory required approximately 25 grams of sample per sample fraction (i.e., SVOCs, herbicides, pesticides, PCBs, dioxins, metals, lipids) for a total sample of 175 to 200 grams per site. These organisms were to be collected using sweep nets and/or other reasonable sampling methods (Appendix C).

Terrestrial invertebrates (primarily grasshoppers and crickets) were collected from all five sites in the immediate vicinity of each of the sampling points where plant and soil material were collected. The terrestrial invertebrate sampling event was conducted between October 7, 2002 and October 10, 2002. Specimens were collected either by sweep net or by hand. The total mass of terrestrial invertebrates required could not be collected at each sample location. While the collection success was variable based on available habitat (e.g., good habitat in Site Q - poor habitat in Sites R and S), the large amount of invertebrates needed could not be satisfied in the allotted sampling time. Therefore, invertebrate samples were composited within a single site, or in some instances, across several contiguous sites. Compositing was conducted only following concurrence with the USEPA oversight contactor, CH2MHill. Following the compositing, there still remained some sampling areas that did not have sufficient biomass to conduct all of the required analyses. Therefore, analyses of the insect samples were prioritized in the following order: 1) dioxins/furans, 2) PCBs, 3) metals, 4) pesticides/herbicides, and 5) SVOCs.

Table 2 is a complete list of sample identities, composite information and analyses conducted on the samples.

2.2.3 SOIL SAMPLING FOR TARGET ANALYTES

The goal of the soil sampling was to obtain an additional eight samples from Site Q for target analyte analysis. It was determined that an insufficient number of samples had been collected in the past from Site Q to accurately determine the extent of the contamination for such a large area. This sampling event was conducted to fill in these data gaps.

Surface soil (0-6 inches from the ground surface) was collected at each location using a decontaminated stainless steel trowel or shovel. These samples were collected on October 7, 2002 by a representative of URS, the RI/FS contractor for the Site. The collected material was then placed into appropriately-labeled sample jars. The eight samples collected from Site Q were analyzed for VOCs, SVOCs, pesticides/herbicides, PCBs, dioxins/furans and metals. Chain-of-custody forms and sample documentation records were retained by URS.

2.2.4 SOIL SAMPLING FOR EARTHWORM TESTS

The goal of this soil sampling was to obtain a sufficient volume of soil at each of the plant/invertebrate sampling locations for use in a laboratory-designed toxicity/bioaccumulation test using earthworms as the test species. Surface soil (0-6 inch interval) was to be collected at each location using a decontaminated stainless steel trowel or shovel and submitted to the bioassay laboratory.

Twenty-eight surface soil samples were collected for the 28-day earthworm bioaccumulation evaluation for measuring the uptake of SVOCs, pesticides and herbicides, PCBs, dioxins and furans, and metals. The samples were collected with decontaminated trowels on October 7 and 8, 2002 from each of the plant/invertebrate sampling locations, and submitted for testing. The sample identities are listed below.

- Site O – Samples: Soil O-1, Soil O-2 and Soil O-3.
- Site P – Samples: Soil P-1, Soil P-2, Soil P-3, and Soil P-4.
- Site Q – Samples: Soil Q-9, Soil Q-10, Soil Q-11, Soil Q-12, Soil Q-13, Soil Q-14, Soil Q-15, Soil Q-16, Soil Q-17, Soil Q-18, Soil Q-19, Soil Q-20.
- Site R – Samples: Soil R-1, Soil R-2, Soil R-3, Soil R-4, and Soil R-5.
- Site S – Sample: Soil S-1.
- Offsite areas – Samples: Soil OS-2, Soil OS-3, and Soil OS-4.

3.0 OVERVIEW OF FIELD PROGRAM ACTIVITIES

The following section describes in greater detail, the field activities conducted during the implementation of the sampling program in the Floodplain Area.

3.1 DAILY SYNOPSIS

The following section summarizes the general circumstances and activities conducted during the course of the Floodplain Area sampling event:

- Day 1, October 7, 2002. AMEC personnel (Mr. Charles R. Harman and Ms. Christy Calhoun) arrived onsite at the project trailer adjacent to Site R at 0815 hours. The weather was clear and dry with a morning temperature of approximately 40° Fahrenheit (F); the afternoon high temperature was approximately 55° F. A representative from URS (Ms. Brandi Higgins) was introduced, and served as an assistant for the course of the field work. Mr. Peter Barrett and Mr. Andy Sprinkle from CH2Mhill were also introduced. Mr. Sprinkle was designated to serve as the oversight person for the field activities. Mr. Barrett departed following a review of the field protocols. The field activities included the collection of the eight surface soil samples from Site Q, setting insect traps, and characterizing the vegetative communities. The collected surface soil samples were shipped to the appropriate analytical laboratories at the end of the field sampling effort.
- Day 2, October 8, 2002. Representatives from AMEC, URS, and CH2Mhill met at the project trailer adjacent to Site R at 0745 hours. The weather was cloudy and dry with a morning temperature of approximately 40° F; the afternoon high temperature was approximately 55° F. The field activities included collecting the vegetative, terrestrial invertebrate, and earthworm bioaccumulation samples; and characterizing the vegetative communities at various locations throughout the site. The collected samples were shipped to the appropriate analytical laboratories at the end of the field sampling effort.

- Day 3, October 9, 2002. Representative of AMEC, URS, and CH2MHill met at the project trailer adjacent to Site R at 0730 hours. The weather was partly cloudy and dry with a morning temperature of approximately 45° F; the afternoon high temperature was approximately 55° F. The field activities included collecting vegetation, terrestrial invertebrate, and earthworm bioaccumulation samples; and characterizing the vegetative communities at various locations throughout the site. The collected samples were shipped to the appropriate analytical laboratories following the field sampling effort.
- Day 4, October 10, 2002. Representatives of AMEC, URS, and CH2MHill met at the project trailer adjacent to Site R at 0730 hours. The weather was partly cloudy and dry with a morning temperature of approximately 45° F; the afternoon high temperature was approximately 60° F. The field activities included collecting terrestrial invertebrate samples and characterizing the vegetative communities at various locations throughout the site. The collected samples were shipped to the appropriate analytical laboratories following the field sampling effort.

3.2 DESCRIPTION OF THE SAMPLING LOCATIONS

The evaluation points for the collection of the ecological data from the Floodplain Area coincided with the surface soil sampling locations utilized in the RI/FS sampling program. An ecological description of each of the sampling points follows:

- Site P-1. This location contained an area of cinders and debris. The habitat at this site was dominated by partridge pea (*Cassia fasciculata*), white heath aster (*Aster pilosus*), common mullein (*Verbascum thapsus*), and eastern cottonwood (*Populus deltoides*);
- Site P-2. The habitat at this location was dominated by Johnson grass (*Sorghum halepense*), smooth sumac (*Rhus glabra*) and crown vetch (*Coronilla varia*);

- Site P-3. The habitat in this area was similar to that of P-2. The predominant vegetative species were crown vetch, white heath aster and Johnson grass;
- Site P-4. The vegetative community at this location was dominated by Johnson grass, tall goldenrod (*Solidago altissima*), slender bush clover (*Lespedeza virginica*), jimsonweed (*Datura stramonium*) and smooth brome (*Bromus inermis*);
- Site O-1. The vegetative community in this area was dominated by Johnson grass and other herbaceous species;
- Site O-2. The habitat at this location was characterized as a tall shrub and grassy environment, dominated by smooth sumac, tall goldenrod, partridge pea, Johnson grass, tall thoroughwort (*Eupatorium altissimum*), slippery elm (*Ulmus rubra*) and poison ivy (*Toxicodendron radicans*). Other species found in this area included Tartarian honeysuckle (*Lonicera tartartica*) and mature eastern cottonwoods;
- Site O-3. The habitat in this area was dominated by grasses, shrubs and herbs such as Tartarian honeysuckle, common mullein, Johnson grass, and barnyard grass (*Echinochloa crusgalli*), as well as some mature eastern cottonwoods;
- Site S-1. The habitat at this location was dominated by mature cottonwoods, white mulberry (*Morus alba*), American elm (*Ulmus americana*), and black locust (*Robinia pseudo-acacia*). Herbaceous species in this area included Johnson grass, fowl meadowgrass (*Glyceria striata*), common pokeweed (*Phytolacca americana*), and Indian grass (*Sorghastrum nutans*). Other species present included Tartarian honeysuckle and trumpet creeper (*Campsis radicans*);
- Site Q-9. This site contained a cleared area dominated by vines encircled on three sides by black willow (*Salix nigra*), and eastern cottonwoods.

- Sites Q-10. This sampling location was dominated by Johnson grass;
- Site Q-13. The habitat at this sampling location was dominated by white mulberry, Johnson grass and scattered eastern cottonwoods;
- Site Q-11. The habitat at this sampling location was dominated by Johnson grass and bushy bluestem (*Andropogon glomeratus*);
- Site Q-12. This habitat at this sampling location was a grassy community dominated by Johnson grass, barnyard grass and common clotbur (*Xanthium chinense*). Samples labeled Q-21 were duplicates of Q-12;
- Site Q-14. The habitat at this sampling location was dominated by Johnson grass, common clotbur, white heath aster and occasional stands of young black willows;
- Site Q-15. The habitat within this sampling location was dominated by herbaceous species such as white heath aster, common clotbur, and small white morning glory (*Ipomoea lacunose*). Isolated black willows were also present;
- Site Q-16. This site contained an early successional forest dominated by black willow, eastern cottonwood and stiff dogwood (*Cornus foemina*). There was limited understory at this site;
- Site Q-17. The habitat at this sampling location was dominated by silver maple (*Acer saccharinum*), with a clearing containing tall goldenrod;
- Site Q-18. The habitat at this sampling location was consisted of a white mulberry grove and white ash (*Fraxinus americana*);

- Sites Q-19 and Q-20. The habitat within these two sampling locations included a row of common clotbur, small white morning glory and northern dropseed (*Sporobolus heterolepis*) alongside of the right-of-way. A forested area was located behind the right-of-way that included black willow, eastern cottonwood and wild cucumber (*Echinocystis lobata*);
- Site R. Site R is an open field surrounded on all four sides by fencing and dominated by various grasses;
- Site OS-2. This site was located east of Site O and east of a set of railroad tracks in a fallow field that had been mowed. The area was dominated by various grasses;
- Site OS-3. This site was located southeast of Site O in the corner of a fence in a fallow field that had been mowed. The area was dominated by various grasses; and
- Site OS-4. This site was located just east of the southern corner of Area Q, this sampling area was bordered by a road to the southwest, a dike to the northwest and a soybean field to the east. Various grasses dominated the area.

Wildlife was also observed either visually or indirectly via calls. The list of species documented as being on site is as follows:


- Gray catbird (*Dumetella carolinensis*), American crow (*Corvus brachyrhynchos*), redwinged blackbird (*Agelaius phoeiceus*), mourning dove (*Zenaida macroura*), black-capped chickadee (*Parus atricapillus*), American kestrel (*Falco sparverius*), red shouldered hawk (*Buteo jamaicensis*), Carolina wren (*Thryothorus ludovicianus*), eastern phoebe (*Sayornis phoebe*), great blue heron (*Ardea herodias*), great egret (*Casmerodius albus*) and American robin (*Turdus migratorius*).


4.0 DEVIATIONS FROM THE SAMPLING PLAN

The following is a list of significant deviations from the sampling plan and the scientific reasoning for the deviations.

- In the original addendum to the sampling plan, the text stated that the earthworm tests were to be conducted for 14 days. However, the toxicity/bioaccumulation tests ran for 28 days as there are no accepted 14-day earthworm test protocols. This was simply an oversight in the text and should have read “28-day earthworm toxicity/bioaccumulation test”. Therefore, no effect on the integrity of the study will result in this deviation.
- The sampling plan had called for the collection of terrestrial invertebrate samples at each of the surface soil sampling locations. However, because of a lack of sufficient biomass, some compositing and prioritization of analyses had to be performed. As this information was being utilized solely to feed more site-specific information into the food chain models, the assumption of similarity of insect tissue residues should not bias or affect the outcome of the food chain modeling.

FIGURES





LEGEND

- Offsite Soil and Upgradient/Groundwater Sampling Locations
- Site-Related Groundwater Sampling Locations
- ⊕ Bedrock Monitoring Well
- ▲ Piezometer Cluster
- ✈ Air Sampling Location
- ▬ Boundary Trench Location
- ▬ Anomaly Trench Location
- ▬ Waste Characterization Boring Location
- △ Leachate Monitoring Well Location

Note: Data from Area 1 background locations will also be considered as background for Area 2

SAUGET AREA 2 SAUGET ILLINOIS		
Figure 2 Sauget Area 2 Sampling Locations		
Date 3/18/03	Project Number 1-7305-0000	Scale AS SHOWN
Source URS	Checked by	Sheet Number
EARTH & ENVIRONMENTAL, INC. 285 Davidson Avenue, Suite 100 Somerset, NJ 08873		

TABLES

TABLE 1

SAUGET AREA 2 VEGETATIVE SPECIES LIST	
<i>Common Name</i>	<i>Scientific Name</i>
Trees	
Ash, Wafer	<i>Ptelea trifoliata</i>
Ash, White	<i>Fraxinus americana</i>
Boxelder	<i>Acer negundo</i>
Cottonwood, Eastern	<i>Populus deltoides</i>
Elm, American	<i>Ulmus americana</i>
Elm, Slippery	<i>Ulmus rubra</i>
Locust, Black	<i>Robinia pseudoacacia</i>
Maple, Silver	<i>Acer saccharinum</i>
Mulberry, White	<i>Morus alba</i>
Sumac, Smooth	<i>Rhus glabra</i>
Walnut, Black	<i>Juglans nigra</i>
Willow, Black	<i>Salix nigra</i>
Shrubs and Vines	
Creeping, Trumpet	<i>Campsis radicans</i>
Cucumber, Wild	<i>Echinocystis lobata</i>
Dogwood, Gray	<i>Cornus foemina</i>
Dogwood, Silky	<i>Cornus amomum</i>
Grape	<i>Vitis sp.</i>
Honeysuckle, Tartarian	<i>Lonicera tartarica</i>
Ivy, Poison	<i>Rhus radicans</i>
Wildflowers	
Artichoke, Jerusalem	<i>Helianthus tuberosus</i>
Aster, White Heath	<i>Aster pilosus</i>
Beardtongue, White	<i>Penstemon digitalis</i>
Bush Clover, Slender	<i>Lespedeza virginica</i>
Camphorweed	<i>Heterotheca subaxillaris</i>
Cleavers	<i>Galium aparine</i>
Clotbur, Common	<i>Xanthium chinense</i>
Dodder, Common	<i>Cuscuta gronovii</i>
Evening Primrose, Common	<i>Oenothera biennis</i>
Fog Fruit, Northern	<i>Phyla lanceolata</i>
Goldenrod, Canada	<i>Solidago canadensis</i>

SAUGET AREA 2 VEGETATIVE SPECIES LIST	
<i>Common Name</i>	<i>Scientific Name</i>
Wildflowers (cont.)	
Goldenrod , Late (Giant)	<i>Solidago gigantea</i>
Goldenrod, Tall	<i>Solidago altissima</i>
Hawkweed	<i>Hieracium gronovii</i>
Horseweed	<i>Erigeron canadensis</i>
Jimsonweed	<i>Datura stramonium</i>
Knotweed (Jumpseed), Virginia	<i>Polygonum virginianum</i>
Lady's Thumb	<i>Polygonum persicaria</i>
Milkweed, Common	<i>Asclepias syriaca</i>
Morning Glory, Ivy-Leaved	<i>Ipomoea hederacea</i>
Morning Glory, Small Red	<i>Ipomoea coccinea</i>
Morning Glory, Small White	<i>Ipomoea lacunose</i>
Mullein, Flannel Plant	<i>Verbascum thapsus</i>
Nettle, Tall	<i>Urtica procera</i>
Pea, Partridge	<i>Cassia fasciculata</i>
Pokeweed	<i>Phytolacca americana</i>
Ragweed, Common	<i>Ambrosia artemisiifolia</i>
Ragweed, Giant	<i>Ambrosia trifida</i>
Snakeroot, White	<i>Eupatorium rugosum</i>
Sneezeweed	<i>Helenium autumnale</i>
Sunflower, Tickseed	<i>Bidens aristosa</i>
Thoroughwort, Tall	<i>Eupatorium altissimum</i>
Tick Trefoil, Panicked	<i>Desmodium paniculatum</i>
Vetch, Crown	<i>Coronilla varia</i>
Water Pepper	<i>Polygonum hydropiper</i>
Grasses, Sedges, Rushes	
Brome, Smooth	<i>Bromus inermis</i>
Bluestem, Bushy	<i>Andropogon gerardi</i>
Dropseed, Tall	<i>Sporobolus heterolepis</i>
Fowl Meadowgrass	<i>Poa palustris</i>
Foxtail, Meadow	<i>Alopecurus pratensis</i>
Grass, Barnyard	<i>Echinochloa crusgalli</i>
Grass, Indian	<i>Sorghastrum nutans</i>
Grass, Johnson	<i>Sorghum halepense</i>
Grass, Manna	<i>Glyceria obtusa</i>
Grass, Orchard	<i>Dactylis glomerata</i>
Sedge, Box	<i>Carex lurida</i>
Sedge, Umbrella	<i>Cyperus strigosus</i>

TABLE 2

TERRESTRIAL INVERTEBRATE SAMPLING MATRIX		
Sample Name	Composite of Sites:	Analyses
IN-Q1	Q-9, Q-10, Q-13, Q-17, Q-18, Q-19 and Q-20	dioxins/furans, SVOCs, metals, pesticides/herbicides, PCBs
IN-Q2	Q-11, Q-12, Q-14, Q-15 and Q-16	dioxins/furans, SVOCs, metals, pesticides/herbicides, PCBs
IN-OS1	Offsite areas OS-2, OS-3 and OS-4	dioxins/furans
IN-ROS1	O-1, O-2, O-3, R-1, R-2, R-3, R-4, R-5, S-1	dioxins/furans, metals, PCBs
IN-P1	P-1, P-2, P-3, P-4	dioxins/furans, metals, PCBs


APPENDIX A

PHOTOGRAPH LOG

SITE P



Photograph 1 Vicinity Sampling Site P-1



Photograph 2 Vicinity Sampling Site P-2



Photograph 3: Vicinity Sampling Site P-3



Photograph 4: Vicinity Sampling Site P-4

SITE O



Photograph 5: Sampling Site O-1



Photograph 6: Sampling Site O-2




Photograph 7 Sampling Site O-3



Photograph 8 Vicinity Site O

Site Q



Photograph 9 Sampling Site Q-9



Photograph 10 Sampling Site Q-10



Photograph 11 Sampling Site Q-10



Photograph 12 Sampling Site Q-10



Photograph 13: Sampling Site Q-11



Photograph 14: Sampling Site Q-12



Photograph 15: Sampling Site Q-12




Photograph 16: Sampling Site Q-12



Photograph 17 Sampling Site Q-12




Photograph 18 Sampling Site Q-12



Photograph 19: Sampling Site Q-13



Photograph 20: Sampling Site Q-13




Photograph 21 Sampling Site Q-14



Photograph 22 Sampling Site Q-14



Photograph 23 Sampling Site Q-14



Photograph 24 Sampling Site Q-15



Photograph 25: Large Pond From Vicinity Sampling Site Q-16



Photograph 26: Large Pond From Vicinity Sampling Site Q-16



Photograph 27: Large Pond From Vicinity Sampling Site Q-16



Photograph 28: Large Pond From Vicinity Sampling Site Q-16



Photograph 29 Large Pond




Photograph 30: Sampling Site Q-17



Photograph 31 Sampling Site Q-18



Photograph 32. Sampling Site Q-18



Photograph 33 Sampling Site Q-18




Photograph 34 Sampling Site Q-19



Photograph 35 Sampling Site Q-19



Photograph 36 Sampling Site Q-19



Photograph 37 Sampling Site Q-19



Photograph 38 Sampling Site Q-20



Photograph 39: Sampling Site Q-20



Photograph 40: Sampling Site Q-20



Photograph 41 Sampling Site Q-20

OFF-SITE AREAS



Photograph 42 Sampling Site OS-2



Photograph 43: Sampling Site OS-3



Photograph 44: Sampling Site OS-4

APPENDIX B

CHAIN OF CUSTODY FORMS

SEVERN
TRENT
SERVICES

ANALYSIS REQUEST AND CHAIN OF CUSTODY RECORD

STL Savannah

☒ **STL Savannah**
5102 LaRoche Avenue
Savannah, GA 31404

Website: www.stl-inc.com
Phone: (912) 354-7858
Fax: (912) 352-0165

☐ Alternate Laboratory Name/Location

Phone:
Fax:

PROJECT REFERENCE <i>Sargent</i>		PROJECT NO.	PROJECT LOCATION (STATE) <i>IL</i>	MATRIX TYPE	REQUIRED ANALYSIS										PAGE <i>1</i>	OF <i>1</i>			
STL (LAB) PROJECT MANAGER		P.O. NUMBER	CONTRACT NO.	COMPOSITE (C) OR GRAB (G) INDICATE AQUEOUS (WATER) SOLID OR SEMISOLID AIR NONAQUEOUS LIQUID (OIL, SOLVENT, ...)	<i>SVOC</i>	<i>Metals</i>	<i>pesticides</i>	<i>PCBs</i>								STANDARD REPORT DELIVERY <input checked="" type="checkbox"/>	DATE DUE _____		
CLIENT (SITE) PM <i>Chuck Harman</i>		CLIENT PHONE <i>732 302 9500</i>	CLIENT FAX <i>9504</i>													EXPEDITED REPORT DELIVERY (SURCHARGE) <input type="checkbox"/>	DATE DUE _____		
CLIENT NAME <i>AMEC Earth+Env.</i>		CLIENT E-MAIL																	
CLIENT ADDRESS <i>285 Davidson Ave Somerset NJ 08873</i>																			
COMPANY CONTRACTING THIS WORK (if applicable)																	NUMBER OF COOLERS SUBMITTED PER SHIPMENT:		
SAMPLE		SAMPLE IDENTIFICATION			NUMBER OF CONTAINERS SUBMITTED										REMARKS				
DATE	TIME																		
<i>10/10/02</i>	<i>0800</i>	<i>IN Q1</i>															<i>1 bottle / sample</i>		
	<i>1030</i>	<i>IN ROS1</i>																	
	<i>0845</i>	<i>IN Q2</i>																	
	<i>1045</i>	<i>IN P1</i>																	
RELINQUISHED BY: (SIGNATURE) <i>[Signature]</i>		DATE <i>10/10/02</i>	TIME <i>1400</i>	RELINQUISHED BY: (SIGNATURE)		DATE	TIME	RELINQUISHED BY: (SIGNATURE)		DATE	TIME	RELINQUISHED BY: (SIGNATURE)		DATE	TIME				
RECEIVED BY: (SIGNATURE) <i>[Signature]</i>		DATE	TIME	RECEIVED BY: (SIGNATURE)		DATE	TIME	RECEIVED BY: (SIGNATURE)		DATE	TIME	RECEIVED BY: (SIGNATURE)		DATE	TIME				



Chain of Custody

Date 10.8.02 Page 1 of 1

DISTRIBUTION: WHITE, CANARY - AMEC Bloassay Lab, PINK - Originator



AMEC San Diego Bloassay Laboratory
5550 Morehouse Drive, Suite B
San Diego, CA 92121
858-458-9044

Chain of Custody

Date 10/5/02 Page 1 of 1

[illegible]



AMEC San Diego Bioassay Laboratory

San Diego, CA 92121

858-458-9044

Chain of Custody

Date 10/5/02 Page 1 of 1

Samples Collected by: <u>Charles Harnan</u>			Mail Report to (if different)			ANALYSIS REQUIRED														
Company <u>AMEC</u> Address <u>285 Davidson Ave Suite 100</u> City <u>Sumerset</u> State <u>NJ</u> Zip <u>08873</u> Contact <u>Charles Harnan</u> Phone No. <u>(732) 302-9500</u>			Company _____ Address _____ City _____ State _____ Zip _____ Contact _____ Phone No. _____			<u>Earthworm Bioassay</u>														
SAMPLE ID	DATE	TIME	MATRIX	CONTAINER TYPE	NUMBER OF CONTAINERS		COMMENTS													
Soil-S-1	10/8/02	1135	Soil	Bag	1			X												
Soil-OS-4	10/8/02	1505	Soil	Bag	1			X												
Soil-R-3	10/8/02	1305	Soil	Bag	1			X												
Soil-OS-2	10/8/02	1430	Soil	Bag	1		X													
PROJECT INFORMATION			SAMPLE RECEIPT			RELINQUISHED BY			RELINQUISHED BY											
CLIENT			TOTAL NO. OF CONTAINERS			(Signature) (Time)			(Signature) (Time)											
PO NO.			CHAIN OF CUSTODY SEALS			(Printed Name) (Date)			(Printed Name) (Date)											
SHIPPED VIA:			REC'D. GOOD CONDITION/COLD			(Company)			(Company)											
SPECIAL INSTRUCTIONS/COMMENTS:			CONFORMS TO RECORD			RECEIVED BY			RECEIVED BY (LABORATORY)											
						(Signature) (Time)			(Signature) (Time)											
						(Printed Name) (Date)			(Printed Name) (Date)											
						(Company)			AMEC Bioassay Lab Log-in No.											

Additional disposal charges may apply.

DISTRIBUTION: WHITE, CANARY - AMEC Bloassay Lab, PINK - Originator



Earth & Environmental, Inc.

AMEC San Diego Bloassay Laboratory

5550 Morehouse Drive, Suite B

San Diego, CA 92121

858-458-9044

Chain of Custody

Date 10/8/02 Page 1 of 1

[illegible]

Additional disposal charges may apply.

DISTRIBUTION: WHITE, CANARY - AMEC Bioassay Lab, PINK - Originator

SERVICES

SEVERN
TRENT
SERVICES

Client Amey			Project Manager Chuck Harmon			Date 10-9-02			Chain of Custody Number 085384		
Address 285 Henderson Hwy Ste 100			Telephone Number (Area Code)/Fax Number			Lab Number			Page 1 of 2		
City Channahon		State MS	Zip Code		Site Contact Chuck Harmon	Lab Contact Pete Haddock		Analysis (Attach list if more space is needed)			
Project Name and Location (State) Swingline IL				Carrier/Waybill Number 1 X							
Contract/Purchase Order/Quote No				Matrix		Containers & Preservatives		Special Instructions/ Conditions of Receipt			


Sample ID No. and Description (Containers for each sample may be combined on one line)	Date	Time	Air	Aqueous	Sed	Soil	"	Unpres	H ₂ SO ₄	HNO ₃	HCl	NaOH	ZnAc/ NaOH	D ₁₀ x
PL-Q 16	10-1-02	0815					✓	✓						X
PL Q-15		0840					✓	✓						
PL Q-14		0900					✓	✓						
PL-Q-9		0920					✓	✓						
PL-Q 20		0940					✓	✓						
PL Q-19		1000					✓	✓						
PL-Q-11		1045					✓	✓						
PL Q 12		1100					✓	✓						
PL-Q-21		1105					✓	✓						
PL-Q 13		1120					✓	✓						
PL-Q 18		1215					✓	✓						
PL-Q-10		1140					✓	✓						

Possible Hazard Identification <input checked="" type="checkbox"/> Non Hazard <input type="checkbox"/> Flammable <input type="checkbox"/> Skin Irritant <input type="checkbox"/> Poison B <input type="checkbox"/> Unknown	Sample Disposal <input type="checkbox"/> Return To Client <input type="checkbox"/> Disposal By Lab <input type="checkbox"/> Archive For _____ Months <small>(A fee may be assessed if samples are retained longer than 3 months)</small>
--	---

Turn Around Time Required

☐ 24 Hours ☐ 48 Hours ☐ 7 Days ☐ 14 Days ☐ 21 Days ☒ Other STD

QC Requirements (Specify)

1 Relinquished By	Date	Time	1 Received By	Date	Time
	10/9/2	1845			
2 Relinquished By	Date	Time	2 Received By	Date	Time
3 Relinquished By	Date	Time	3 Received By	Date	Time

Comments

DISTRIBUTION WHITE Stays w th the Sample CANARY Returned to Client with Report PINK Field Copy

**SEVERN
TRENT
SERVICES**

Severn Trent Laboratories, Inc.

STL-4124 (1200)

[illegible]

Possible Hazard Identification			Sample Disposal			(A fee may be assessed if samples are retained longer than 3 months)			
<input checked="" type="checkbox"/> Non-Hazard	<input type="checkbox"/> Flammable	<input type="checkbox"/> Skin Irritant	<input type="checkbox"/> Poison B	<input type="checkbox"/> Unknown	<input type="checkbox"/> Return To Client	<input type="checkbox"/> Disposal By Lab	<input type="checkbox"/> Archive For _____ Months		
Turn Around Time Required					QC Requirements (Specify)				
<input type="checkbox"/> 24 Hours	<input type="checkbox"/> 48 Hours	<input type="checkbox"/> 7 Days	<input type="checkbox"/> 14 Days	<input type="checkbox"/> 21 Days	<input checked="" type="checkbox"/> Other <u>570</u>				
1 Relinquished By <u>[Signature]</u>			Date <u>10/9/20</u>	Time <u>1845</u>	1 Received By			Date	Time
2 Relinquished By			Date	Time	2 Received By			Date	Time
3 Relinquished By			Date	Time	3 Received By			Date	Time

Comments

DISTRIBUTION WHITE - Stays with the Sample CANARY Returned to Client with Report PINK Field Copy

SERVICES

SEVERN
TRENT
SERVICES

Client Amec	Project Manager Chuck Harman	Date 10-8-02	Chain of Custody Number 085386
Address 285 Davidson Ave, Suite 100	Telephone Number (Area Code)/Fax Number	Lab Number	Page <u>1</u> of <u>2</u>

City Somerset	State NJ	Zip Code 07945	Site Contact	Lab Contact	Analysis (Attach list if more space is needed)
------------------	-------------	-------------------	--------------	-------------	--


[illegible][illegible]

Sample I D No and Description (Containers for each sample may be combined on one line)	Date	Time	Air	Aqueous	Sed	Soil	Plant	Unpres	H ₂ SO ₄	HNO ₃	HCl	NaOH	ZnAc ₂	NaOH	Plox
PL-P-1	10-8-02	0845					+	+							X
PL-P-2		0910					+	+							
PL-P-3		0930					+	+							
PL-P-4		0815					+	+							
PL-O-1		1010					+	+							
PL-O-2		1030					+	+							
PL-O-3		1105					+	+							
PL-S-1		1135					+	+							
PL-R-1		1335					+	+							
PL-R-2		1550					+	+							
PL-R-3		1305					+	+							
PL-R-4		1610					+	+							

Possible Hazard Identification					Sample Disposal			(A fee may be assessed if samples are retained longer than 3 months)
<input checked="" type="checkbox"/> Non-Hazard	<input type="checkbox"/> Flammable	<input type="checkbox"/> Skin Irritant	<input type="checkbox"/> Poison B	<input type="checkbox"/> Unknown	<input type="checkbox"/> Return To Client	<input type="checkbox"/> Disposal By Lab	<input type="checkbox"/> Archive For _____ Months	

Turn Around Time Required
☐ 24 Hours ☐ 48 Hours ☐ 7 Days ☐ 14 Days ☐ 21 Days ☒ Other STO

QC Requirements (Specify)

1 Relinquished By 	Date 10/8/02	Time 1705	1 Received By	Date	Time
--	-----------------	--------------	---------------	------	------

2 Relinquished By	Date	Time	2 Received By	Date	Time

3 Relinquished By	Date	Time	3 Received By	Date	Time

Comments

DISTRIBUTION WHITE - Stays with the Sample CANARY - Returned to Client with Report PINK - Field Copy

SEVERN
TRENT
SERVICES

Severn Trent Laboratories, Inc.

STL-4124 (1200)

[illegible]

Possible Hazard Identification			Sample Disposal			(A fee may be assessed if samples are retained longer than 3 months)		
<input checked="" type="checkbox"/> Non-Hazard <input type="checkbox"/> Flammable <input type="checkbox"/> Skin Irritant <input type="checkbox"/> Poison B <input type="checkbox"/> Unknown			<input type="checkbox"/> Return To Client <input type="checkbox"/> Disposal By Lab <input type="checkbox"/> Archive For _____ Months					
Turn Around Time Required			QC Requirements (Specify)					
<input type="checkbox"/> 24 Hours <input type="checkbox"/> 48 Hours <input type="checkbox"/> 7 Days <input type="checkbox"/> 14 Days <input type="checkbox"/> 21 Days <input checked="" type="checkbox"/> Other <u>SLD</u>								
1 Relinquished By <u>[Signature]</u>			Date <u>10/8/02</u>		Time <u>1705</u>		1 Received By _____	
			Date _____		Time _____		Date _____	
2 Relinquished By _____			Date _____		Time _____		2 Received By _____	
			Date _____		Time _____		Date _____	
3 Relinquished By _____			Date _____		Time _____		3 Received By _____	
			Date _____		Time _____		Date _____	

Comments

DISTRIBUTION WHITE - Stays with the Sample CANARY - Returned to Client with Report PINK - Field Copy

**SEVERN
TRENT
SERVICES**

ANALYSIS REQUEST AND CHAIN OF CUSTODY RECORD

STL Savannah

☒ **STL Savannah**
5102 LaRoche Avenue
Savannah GA 31404

Website www.stl-inc.com
Phone (912) 354-7858
Fax (912) 352-0165

☐ Alternate Laboratory Name/Location

Phone
Fax

PROJECT REFERENCE <i>50007 Area 2</i>		PROJECT NO	PROJECT LOCATION (STATE)	MATRIX TYPE	REQUIRED ANALYSIS										PAGE	OF	
STL (LAB) PROJECT MANAGER <i>Michelle Owens</i>		PO NUMBER	CONTRACT NO	COMPOSITE (C) OR GRAB (G) INDICATE AQUEOUS (WATER) SOLID OR SEMISOLID AIR NONAQUEOUS LIQUID (OIL SOLVENT)	<i>SUDC</i>	<i>-AL Methyl</i>	<i>Pest / Herb</i>	<i>PCBs</i>									STANDARD REPORT DELIVERY <input checked="" type="checkbox"/>
CLIENT (SITE) PM <i>Chuck N...</i>		CLIENT PHONE <i>772 302 9500</i>	CLIENT FAX														DATE DUE
CLIENT NAME <i>AMEC</i>		CLIENT E MAIL															EXPEDITED REPORT DELIVERY (SURCHARGE) <input type="checkbox"/>
CLIENT ADDRESS <i>285 2nd Ave Somerset, NJ</i>		COMPANY CONTRACTING THIS WORK (if applicable)															DATE DUE
SAMPLE		SAMPLE IDENTIFICATION		NUMBER OF CONTAINERS SUBMITTED										REMARKS			
DATE	TIME																
<i>10/9/02</i>	<i>1100</i>	<i>PL-Q-12</i>		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>				<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>					<i>Paint Tissue</i>
	<i>1105</i>	<i>PL-Q-21</i>															
	<i>1120</i>	<i>PL-Q-13</i>															
	<i>1215</i>	<i>PL-Q-18</i>															
	<i>1140</i>	<i>PL-Q-10</i>															
<input checked="" type="checkbox"/>	<i>1235</i>	<i>PL-Q-17</i>															
RELINQUISHED BY (SIGNATURE) <i>Empty Containers</i>		DATE	TIME	RELINQUISHED BY (SIGNATURE) <i>[Signature]</i>		DATE <i>10/09/02</i>	TIME <i>1845</i>	RELINQUISHED BY (SIGNATURE)		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME		
RECEIVED BY (SIGNATURE) <i>Empty Containers</i>		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME		

RECEIVED FOR LABORATORY BY (SIGNATURE)	DATE	TIME	RECEIVED BY (SIGNATURE)	DATE	TIME	RECEIVED BY (SIGNATURE)	DATE	TIME
--	------	------	-------------------------	------	------	-------------------------	------	------

[illegible]**CLIENT'S FIELD COPY**

Serial number 548000

SEVERN
TRENT
SERVICES

ANALYSIS REQUEST AND CHAIN OF CUSTODY RECORD

STL Savannah

STL Savannah
5102 LaRoche Avenue
Savannah, GA 31404Website: www.stl-inc.com
Phone: (912) 354-7858
Fax: (912) 352-0165

Alternate Laboratory Name/Location

Phone
Fax:

PROJECT REFERENCE <i>Souget Area 2</i>		PROJECT NO	PROJECT LOCATION (STATE)	MATRIX TYPE	REQUIRED ANALYSIS										PAGE	OF		
STL (LAB) PROJECT MANAGER		PO NUMBER	CONTRACT NO	COMPOSITE (C) OR GRAB (G) INDICATE AQUEOUS (WATER) SOLID OR SEMISOLID AIR NONAQUEOUS LIQUID (OIL, SOLVENT,)	SVOC	Metal	ACB	Pest/Herb									STANDARD REPORT DELIVERY <input checked="" type="checkbox"/>	DATE DUE _____
CLIENT (SITE) PM <i>AMEC</i>		CLIENT PHONE <i>732-392-9500</i>	CLIENT FAX															
CLIENT NAME <i>C. R. Norman</i>		CLIENT E-MAIL																
CLIENT ADDRESS <i>285 Davidson Ave, Suite</i>																		
COMPANY CONTRACTING THIS WORK (if applicable)				PRESERVATIVE										NUMBER OF COOLERS SUBMITTED PER SHIPMENT				
SAMPLE		SAMPLE IDENTIFICATION		NUMBER OF CONTAINERS SUBMITTED										REMARKS				
DATE	TIME																	
10/8	0815	PL-P-4		X														Plant tissue
	0845	PL-P-1		X														samples
	0910	PL-P-2		X														
	0930	PL-P-3		X														
	1010	PL-O-1		X														
	1030	PL-O-2		X														
	1105	PL-O-3		X														
	1135	PL-S-1		X														
		PL-R-3																
		PL-R-5																
RELINQUISHED BY (SIGNATURE) EMPTY CONTAINERS		DATE	TIME	RELINQUISHED BY (SIGNATURE) <i>C. R. Norman</i>		DATE <i>10/8/02</i>	TIME <i>1700</i>	RELINQUISHED BY (SIGNATURE)		DATE	TIME	RELINQUISHED BY (SIGNATURE)		DATE	TIME			
RECEIVED BY (SIGNATURE) EMPTY CONTAINERS		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME			

SEVERN

TRENT

SERVICES

ANALYSIS REQUEST AND CHAIN OF CUSTODY RECORD

STL Savannah



STL Savannah

5102 LaRoche Avenue
Savannah, GA 31404

Website www.stl-inc.com

Phone: (912) 354-7858

Fax: (912) 352-0165

Alternate Laboratory Name/Location

Phone

Fax

PROJECT REFERENCE <i>Sanger Area 2</i>		PROJECT NO	PROJECT LOCATION (STATE)	MATRIX TYPE	REQUIRED ANALYSIS										PAGE	OF		
STL (LAB) PROJECT MANAGER <i>Michelle Owens</i>		PO NUMBER	CONTRACT NO	COMPOSITE (C) OR GRAB (G) INDICATE AQUEOUS (WATER) SOLID OR SEMISOLID AIR NONAQUEOUS LIQUID (OIL, SOLVENT, ...)	<i>Metals</i> <i>SUDCS</i> <i>Pest/Herb</i> <i>PCBs</i>	PRESERVATIVE									STANDARD REPORT DELIVERY <input checked="" type="checkbox"/>		DATE DUE _____	
CLIENT (SITE) PM <i>C R NARMAN</i>		CLIENT PHONE <i>732-302-9500</i>	CLIENT FAX												EXPEDITED REPORT DELIVERY (SURCHARGE) <input type="checkbox"/>		DATE DUE _____	
CLIENT NAME <i>AMEC</i>		CLIENT E-MAIL																
CLIENT ADDRESS <i>285 Davidson</i>																		
COMPANY CONTRACTING THIS WORK (if applicable)																	NUMBER OF COOLERS SUBMITTED PER SHIPMENT <i>2</i>	
SAMPLE		SAMPLE IDENTIFICATION			NUMBER OF CONTAINERS SUBMITTED										REMARKS			
DATE	TIME																	
<i>10/8/02</i>	<i>1205</i>	<i>PL-R-3</i>			<i>X</i>	<i>X</i>				<i>X</i>	<i>X</i>	<i>X</i>	<i>X</i>				<i>Plant Tissue</i>	
	<i>1305</i>	<i>PL-R-5</i>															<i>Samples</i>	
	<i>1335</i>	<i>PL-R-L</i>																
	<i>1410</i>	<i>PL-OS-3</i>																
	<i>1430</i>	<i>PL-OS-2</i>																
	<i>1505</i>	<i>PL-OS-4</i>																
	<i>1550</i>	<i>PL-R-2</i>																
<i>↓</i>	<i>1610</i>	<i>PL-R-4</i>								<i>X</i>	<i>X</i>	<i>X</i>	<i>X</i>				<i>↓</i>	
<div style="position: absolute; top: 0; left: 0; width: 100%; height: 100%; border: 1px solid black; transform: rotate(-30deg); opacity: 0.5;"></div>																		
RELINQUISHED BY (SIGNATURE) EMPTY CONTAINERS		DATE	TIME	RELINQUISHED BY (SIGNATURE) <i>C R Narmann</i>		DATE <i>10/8/02</i>	TIME <i>1705</i>	RELINQUISHED BY (SIGNATURE)		DATE	TIME	RELINQUISHED BY (SIGNATURE)		DATE	TIME			
RECEIVED BY (SIGNATURE) EMPTY CONTAINERS		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME	RECEIVED BY (SIGNATURE)		DATE	TIME			

APPENDIX C

VOLUME 4

TERRESTRIAL BIOTA SAMPLING

PROJECT PLANS

ADDENDUM

VOLUME 4
TERRESTRIAL BIOTA SAMPLING PROJECT PLANS

Revision 2 - Addendum

The following changes are noted in the Terrestrial Biota Sampling Project Plans (Volume 4), based on the results of the August 2, 2001 meeting with USEPA and follow-up discussions with Dr. James Chapman of the USEPA. This Addendum will constitute the only documentation of these changes and will be considered an incorporated part of the Volume 4 Sampling Project Plans. The changes are noted as follows:

1. Aside from qualitative descriptions made solely for purposes of site characterization, no vegetative community structure assessment will be made.
2. Eight additional soil samples will be collected from the southern end of Site Q. The locations of these samples will be verified during the field reconnaissance and will be biased towards areas of viable wildlife habitat. Soil samples from these locations will be collected from the surface interval (0 – 6" below ground) and will be analyzed for the standard parameters. Biological sampling (i.e., vegetative samples for residue analysis) will also be conducted at each of the eight locations.
3. Earthworms will no longer be collected from each of the surface soil locations throughout the five Sites. Instead, soil samples will be collected from each location and submitted to a laboratory for a 14-day earthworm toxicity/bioaccumulation test using laboratory provided earthworms (*Eisenia foetida*). Following the completion of the test, earthworms from the test will be analyzed in the laboratory for tissue residue. In place of the field collected earthworms, a composite sample of field collected terrestrial invertebrates (including beetles, crickets, and grasshoppers, slugs, snails and lepidopteran larvae). These organisms will be collected using sweep nets and other reasonable sampling methodologies. One composite sample from each soil sampling location will be submitted for laboratory analysis.

4. Biological sampling (including vegetative and invertebrate) will be conducted at those locations chosen for background surface soil sampling locations.